N

El Sub Sta

MOTS

Ornamental Shrub Planting
2 no. *Genista lydia*
3 no. *Hebe* 'Green Globe'
3 no. *Lavandula angustfolia* 'Hidcote'
2 no. *Santolina chamaecyparissus*

1 no. *Crataegus monogyana*
1 no. *Acer campestre*
1 no. *Quercus robur*
1 no. *Betula pendula*
1 no. *Alnus glutinosa*

Ornamental Shrub Planting
2 no. *Genista lydia*
3 no. *Hebe* 'Green Globe'
3 no. *Lavandula angustfolia* 'Hidcote'
2 no. *Santolina chamaecyparissus*

BUS ONLY

BUS ONLY

Climber Planting
XX no. Hydrangea anomala petiolaris

1 no. *Acer campestre*

Ornamental Shrub Planting
4 no. *Genista lydia*
9 no. *Hebe* 'Green Globe'
11 no. *Lavandula angustfolia* 'Hidcote'
6 no. *Santolina chamaecyparissus*

1 no. *Crataegus monogyana*

1:250 METRIC

10m 0 10m 20m 30m 40m

KEY

Planning Boundary

Existing Landscape

Tree (retained)
Refer to Drawing:
JG18198 Topo 3D 01-02 'Topographical Survey'

Tree (removed)
Refer to drawing:
B2350500-JAC-DRG-HA-0004-0005 'Site Clearance'

Proposed Landscape

Trees
Refer to report: BRT-TG-XX-ZZ-SH-LS-300 'Written landscape Specification' for full planting specifications and schedules

Ornamental Shrub Planting
Refer to report: BRT-TG-XX-ZZ-SH-LS-300 'Written landscape Specification' for full planting specifications and schedules
Gross Area: 0.0044ha

Amenity Grass Seeding
Gross Area: 0.0485 ha

Wildflower Meadow Seeding
Gross Area: 0.0719 ha

Wetland/Pond Meadow Seeding
Gross Area: 0.0114 ha

Climber Planting
Gross Area: 0.0023 ha

Grassland Enhancement Areas
Gross Area: 0.1063 ha

Reed Bed
Gross Area: 0.1012 ha

Hard Landscaping
Gross Area: 0.1047 ha

Gabion Wall

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following :

CONSTRUCTION
A000 - Identify and locate existing services. All buried services to be isolated / protected prior to start of works. Ensure adequate separation of construction activities and adjacent live carriageways.
Implement safety measures when working in excavations, confined spaces and traffic areas.
Implement appropriate safety measures when working around and over bodies of water and reed beds.
Implement measures to protect all wildlife encountered, especially protected species.

MAINTENANCE / CLEANING
- As above

DECOMMISSIONING / DEMOLITION
- As above

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement

Rev	Date	Description	Prod.	Chk.	Rev.	App.
P01	12.07.24	Planning application submission	JFS	BP	CJ	LK

Kent County Council

Project:
Fastrack Full Network
Bean Road Tunnel

Site
Bluewater
Greenhithe
Kent
DA99ST

Client
Kent County Council

ARCADIS

Registered office:
80 Fenchurch Street
London
EC3M 4BY

Coordinating office:
80 Fenchurch Street
London
EC3M 4BY
Tel: 44 (0)20 7812 2000

www.arcadis.com
© Copyright reserved

Drawing Title:
PROPOSED LANDSCAPE PLAN
BEAN ROAD TUNNEL

DO NOT SCALE

Scale: 1:250 @A1

Suitability Description:
PLANNING APPLICATION

Drawing Number: BRT-TG-XX-ZZ-DR-LS-3005

Revision: P01